

**ERECTION OF TEMPORARY SLOPED / FLAT / G.I. SHEET PANDAL / STALL ARRANGEMENTS ON RENTAL BASIS FOR PROVIDING MOVEMENTS FOR PUBLIC, KEEPING PLANTS IN CONNECTION WITH FLOWER SHOW ' 2016 AT BOTANICAL GARDEN, PUDUCHERRY - FROM 22.01.2016 TO 24.01.2016 THREE DAYS.**

SL. NO.	DESCRIPTION	QTY.	RATE IN FIGURES	RATE IN WORDS	PER	AMOUNT
1	Hire charges for erection and removing of temporary sloped GI sheet roof stage /dias size of 20'0" x 20'0", using with vertical casuarina poles of 100mm to 50mm dia at suitable intervals and rafters of bamboo / casuarina / eucalyptus of required dia at spacing not exceeding 50cm in both directions as directed. The height of roof shall not be less than 4m in front and 3m at rear above the wooden platform and covered with taur-pauline suitably for conducting culture programmes including separate handrail for steps up and down and neatly covered with cada cloth decorated with colour papers in the ceiling all over as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from	1.00 Job			Job	
2	Hire charges for erection and removing of temporary sloped pandal / stalls using galvanized iron (GI) sheets corrugated sheets with vertical casuarina poles of 100mm to 50mm dia at suitable intervals of 3m and rafters of bamboo / casuarina / eucalyptus of required dia at spacing not exceeding 50cm in both directions. The height of roof shall not be less than 3m in front and 2.4m at rear with suitable barricading in the front side of stall. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from					
	a. Roof area	1500 sqm			sqm	
	b. Side area	800 sqm			sqm	

3	Hire charges for fixing and removing wooden benches using 20mm thick planks of 30cm width resting on casuarina props of 5cm to 10cm dia to the height of 75cm to 180cm as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	1000 rmt.			Rmt.	
4	Hire charges for erection and removing 1.50m height barricading arrangements with casuarina vertical poles of 100mm dia at 1.50m intervals and braced with 4 (four) rows of casuarina poles of 80mm dia tied with necessary ropes / coir. The vertical pole fixed to a depth of 60cm in earth / concrete surface etc., (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	1000 rmt			Rmt.	
5	Hire charges for erection and removing 1.50m height barricading arrangements with iron pipes of 40 to 100mm dia. at 1.50m intervals and braced with iron pipes with necessary bolt and net or ready made iron barricade structure as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	1000 rmt.			Rmt.	
6	Hire charges for fixing and removing cada white cloth / shade net for ceiling sides and benches of stall, wherever necessary neatly fixed complete as per instructions of Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW- 2016 from 22.01.2016 to 24.01.2016).	2000 sqm			Sqm	

7	Hire charges of laying and removing good synthetic mat as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and laying and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	100 sqm				sqm
8	Hire charges for PVC chairs, as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	500 Nos.				Each
9	Hire charges for laying and removing of wooden / steel tables of size 6ø * 1 ½ø * 2 ½ø as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	200 Nos.				Each
10	Hire charges for fixing and removing 3m GI corrugated sheet barricading along the periphery of the FLOWER SHOW area with casuarina poles to a height of 2.40m above GL and fixing firmly with ground with suitable intervals not exceeding 1m and braced with 5 Nos. of horizontal and braced with 5 Nos. of horizontal (ie., not more than 60cm apart) as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	3000 sqm				sqm
11	Hire charges for fixing and removing of VIP chairs. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	20 Nos.				Each

12	Hire charges for installation and removing of Kuthuvilakku not less than 400 height for the purpose of function as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	1 No.			Each
13	Hire charges for installation and removing of teapoy table. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	2 Nos.			Each
14	Hire charges for laying and removing table cloth of design and good finished type over the teapoy. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	2 Nos.			Each
15	Hire charges for installation and removing of good working air cooler. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW- 2016 from 22.01.2016 to 24.01.2016.).	2 Nos.			Each
16	Hire charges for installation and removing of good working pedestal fan. (The rate includes materials, labour and to and fro transportation and providing and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	5 Nos.			Each
17	Supply and fixing of digital flex screen of approved design as back drop to the size of 2000 * 1000 all as directed by the Engineer-in-charge.	200 sqft.			Sqft.
18	Hire charges for erection and removing special shamiana for VVIP and VIP refreshment spot all as directed by the Engineer-in-charge. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).				
	a. Roof area	180 sqm			sqm

	b. Side wall area	150 sqm			sqm	
19	Hire charges for erection and removing suitable fancy fencing in front of stage as directed by the Engineer-in-charge. . (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	1 job			Job	
20	Hire charges for fixing and removing ply wood platform with planks for Rangoli arrangements / stalls.	250 sqm			sqm	
21	Hire charges for supply of Podium for stage.	1 No.			Each	
22	Hire charges for erection and removing of food court covered with G.I. sheet, G.I. sheet roofing of height 14'0" with raised wooden flooring, stall partitioning with G.I. sheet to the height of 3' 0" to 4'0" (size 20'0" x 150'0"). (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	3000 sqft.			sqft.	
23	Hire charges for providing main entrance arch for four sides covering with decorative arrangements, as directed by the Engineer-in-charge of width 35' and height 14' + 6'.	1 Job.			Job	
24	Hire charges for erection and renewing of Departmental Stalls with G.I.sheet roofing to a height of 14'0" with raised wooden flooring and sides covered with G.I. sheet. (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	6000 sqft.			Sqft.	
25	Hire charges for partition of stall with aluminium fabricated board stall size 10' x 10' as directed by the Engineer-in-charge (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016).	60 Nos.			Each	

26	Hire charges for erection and removing of control room for Police, Fire Service, Office, First-aid-Rooms with GI sheet roofing of height 14'0". (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	1500 sqft			Sqft.
27	Hire charges for erection and removing of Arabian tent with side covering necessary complete labour charges-20'0"x20'0" (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.).	1 No.			Each
28	Hire charges for erection and removing of shade net shed of size 80'0" x100'0" with 14'0" height supported with 'A' type MS tubular / angular truss . (The rate includes materials, labour and to and fro transportation and erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.)	8000 sqft			sqft.
29	Hire charges for erection and removing of shamiana of size 20'0"x15'0" with 20'0" height for Machinaries Stall with side cladding, raised wooden platform (10 Nos.). (The rate includes materials, labour, to and fro transportation, erection and removing period including the three days of FLOWER SHOW-2016 from 22.01.2016 to 24.01.2016.)	3000 sqft.			Sqft.